



OFFICE OF THE PRINCIPAL / SECRETARY

☎ : 03252-240251 & 9083255098

E-mail : mgclalpur@yahoo.co.in

www.mahatmagandhicollege.org

# MAHATMA GANDHI COLLEGE

( NAAC Accredited Grade - "B<sup>+</sup>" w.e.f. 16, 09, 2016 )

**LALPUR • P.O.-DALDALI • DIST.-PURULIA • PIN-723130 • (W. B.)**

Ref. No. ....

Date.....

## NOTICE

Ref. No. 08/MGC/Tender/2022-23

Dt. 18.07.2023

Quotations are invited in sealed envelopes for the renovation of the Toilet Block of Block – D of Mahatma Gandhi College. Quotations are to reach the college office by 27.07.23. The plan estimate is attached below.


Principal,  
Mahatma Gandhi College  
Lalpur, Daldali, Purulia.



**Estimation for the construction cost of existing building of D Block(Toilet block renovation) M.G College Lalpur, Dist.- Purulia. Estimate is based on P.W.D schedule of rates.**

Item Code.	Description of Work	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
1	Brickwork with 1" class bricks in cement mortar 6:1 250mm th	cum	0.35	4545.00	1,590.75
2	Plaster (to wall, floor, ceiling ect.) with sand and cement mortar ..... 15 mm th(1:6)	sqm	2.80	137.00	383.60
<b>INTERIOR GRADE ACRYLIC DISTEMPER PAINT</b>					
3	Providing 2 coats of first quality Acrylic distemper of approved colour to all internal walls over a coat of approved primer cement based / distemper / Alkali resistant primer including preparation of surface through cleaning and wetting and applying ready made putty 2mm to 3 mm thick of approved brand as per manufacturer's specification fully to give a smooth and even surface before and subsequent application and making good all small holes of nails, open joints and minor defects of every kind after application of priming coat, all as per specification and as directed.				
	Luxury Quality ( two coats)	Sqm	64.00	76.00	4,864.00
4	Supplying fitting and fixing 1st quality ceramic tiles in walls & floor to match with the .....				
	(A) Floor				
	With Sand Cement Mortar (1:4) 20 mm thick & 2 mm thick	sqm	11.20	731.00	8,187.20
	(B) Wall				
	With Sand Cement Mortar (1:3) 15 mm thick & 2 mm thick	sqm	20.00	740.00	14,800.00
5	Rendering the surface of wall and ceiling ..... wall putty	sqm	64.00	122.00	7,808.00
6	Comode	no	2.00	3965.00	7,930.00
7	Wash Besin	no	2.00	1374.00	2,748.00
8	Urinal	no	2.00	820.00	1,640.00
9	Flushing cistern	no	2.00	1500.00	3,000.00
10	Bib cock	no	2.00	689.00	1,378.00
11	Waste pipe	no	2.00	60.00	120.00
	Supplying fitting and fixing PVC door frame	Rm	10.40	279.00	2,901.60
12	P.V.C Door Shutter	Sqm	3.80	2287.00	8,690.60
13	Exhaust Fan	no	2.00	1489.00	2,978.00
14	Window glass	no	2.00	700.00	1,400.00
	CPVC Pipe(25mm)	m	8.00	200.00	1,600.00
	CpVC Pipe(15mm)	m	12.00	122.00	1,464.00
	<b>TOTAL</b>				<b>73,483.75</b>
	Add: Contingency @ 3%	Rs.			2,204.51
	<b>Estimated Cost</b>	Rs.			<b>75,688.26</b>
		Rs.	Say		<b>75688.00</b>

**Rs. Seventy Five thousand six hundred Eighty Eight only**

  
 J.E (P.W.D.)  
 Hara Dev Block